

ASME OM-2012
(Revision of ASME OM-2009)

Operation and Maintenance of Nuclear Power Plants

AN AMERICAN NATIONAL STANDARD



**The American Society of
Mechanical Engineers**

ASME OM-2012
(Revision of ASME OM-2009)

Operation and Maintenance of Nuclear Power Plants

AN AMERICAN NATIONAL STANDARD



**The American Society of
Mechanical Engineers**

Two Park Avenue • New York, NY • 10016 USA

Date of Issuance: April 8, 2013

The next edition of this Code is scheduled for publication in 2015.

ASME issues written replies to inquiries concerning interpretations of technical aspects of this Code. Periodically certain actions of the ASME OM Committee may be published as Code Cases. Code Cases and interpretations are published on the ASME Web site under the Committee Pages at <http://cstools.asme.org/> as they are issued.

Errata to codes and standards may be posted on the ASME Web site under the Committee Pages to provide corrections to incorrectly published items, or to correct typographical or grammatical errors in codes and standards. Such errata shall be used on the date posted.

The Committee Pages can be found at <http://cstools.asme.org/>. There is an option available to automatically receive an e-mail notification when errata are posted to a particular code or standard. This option can be found on the appropriate Committee Page after selecting “Errata” in the “Publication Information” section.

ASME is the registered trademark of The American Society of Mechanical Engineers.

This code or standard was developed under procedures accredited as meeting the criteria for American National Standards. The Standards Committee that approved the code or standard was balanced to assure that individuals from competent and concerned interests have had an opportunity to participate. The proposed code or standard was made available for public review and comment that provides an opportunity for additional public input from industry, academia, regulatory agencies, and the public-at-large.

ASME does not “approve,” “rate,” or “endorse” any item, construction, proprietary device, or activity.

ASME does not take any position with respect to the validity of any patent rights asserted in connection with any items mentioned in this document, and does not undertake to insure anyone utilizing a standard against liability for infringement of any applicable letters patent, nor assumes any such liability. Users of a code or standard are expressly advised that determination of the validity of any such patent rights, and the risk of infringement of such rights, is entirely their own responsibility.

Participation by federal agency representative(s) or person(s) affiliated with industry is not to be interpreted as government or industry endorsement of this code or standard.

ASME accepts responsibility for only those interpretations of this document issued in accordance with the established ASME procedures and policies, which precludes the issuance of interpretations by individuals.

No part of this document may be reproduced in any form,
in an electronic retrieval system or otherwise,
without the prior written permission of the publisher.

The American Society of Mechanical Engineers
Two Park Avenue, New York, NY 10016-5990

Copyright © 2013 by
THE AMERICAN SOCIETY OF MECHANICAL ENGINEERS
All rights reserved
Printed in U.S.A.

CONTENTS

(A Detailed Contents Precedes Each Division)

Foreword	iv
Preparation of Technical Inquiries	v
Committee Roster	vii
Preface	ix
Summary of Changes	xi
Division 1 OM Code: Section IST	1
Division 2 OM Standards	109
Division 3 OM Guides	309

DIVISION 1: OM CODE: SECTION IST

CONTENTS

SUBSECTION ISTA	GENERAL REQUIREMENTS	6
ISTA-1000	Introduction	6
ISTA-1100	Scope	6
ISTA-1200	Jurisdiction	6
ISTA-1300	Application	6
ISTA-1400	Referenced Standards and Specifications	6
ISTA-1500	Owner's Responsibilities	6
ISTA-1600	Accessibility	7
ISTA-2000	Definitions	7
ISTA-3000	General Requirements	8
ISTA-3100	Test and Examination Program	8
ISTA-3200	Administrative Requirements	8
ISTA-3300	Corrective Actions	9
ISTA-4000	Instrumentation and Test Equipment	9
ISTA-4100	Range and Accuracy	9
ISTA-4200	Calibration	9
ISTA-5000	To Be Provided at a Later Date	9
ISTA-6000	To Be Provided at a Later Date	9
ISTA-7000	To Be Provided at a Later Date	9
ISTA-8000	To Be Provided at a Later Date	9
ISTA-9000	Records and Reports	9
ISTA-9100	Scope	9
ISTA-9200	Requirements	9
ISTA-9300	Retention	10
Table		
ISTA-1400-1	Referenced Standards and Specifications	6
SUBSECTION ISTB	INSERVICE TESTING OF PUMPS IN LIGHT-WATER REACTOR NUCLEAR POWER PLANTS — PRE-2000 PLANTS	11
ISTB-1000	Introduction	11
ISTB-1100	Applicability	11
ISTB-1200	Exclusions	11
ISTB-1300	Pump Categories	11
ISTB-1400	Owner's Responsibility	11
ISTB-2000	Supplemental Definitions	11
ISTB-3000	General Testing Requirements	11
ISTB-3100	Preservice Testing	11
ISTB-3200	Inservice Testing	12
ISTB-3300	Reference Values	12
ISTB-3400	Frequency of Inservice Tests	13
ISTB-3500	Data Collection	13

ISTB-4000	To Be Provided at a Later Date	14
ISTB-5000	Specific Testing Requirements	14
ISTB-5100	Centrifugal Pumps (Except Vertical Line Shaft Centrifugal Pumps)	14
ISTB-5200	Vertical Line Shaft Centrifugal Pumps	16
ISTB-5300	Positive Displacement Pumps	18
ISTB-6000	Monitoring, Analysis, and Evaluation	20
ISTB-6100	Trending	20
ISTB-6200	Corrective Action	20
ISTB-6300	Systematic Error	21
ISTB-6400	Analysis of Related Conditions	21
ISTB-7000	To Be Provided at a Later Date	21
ISTB-8000	To Be Provided at a Later Date	21
ISTB-9000	Records and Reports	21
ISTB-9100	Pump Records	21
ISTB-9200	Test Plans	21
ISTB-9300	Record of Tests	21
ISTB-9400	Record of Corrective Action	21
Figure		
ISTB-5223-1	Vibration Limits	18
Tables		
ISTB-3000-1	Inservice Test Parameters	12
ISTB-3400-1	Inservice Test Frequency	13
ISTB-3510-1	Required Instrument Accuracy	13
ISTB-5121-1	Centrifugal Pump Test Acceptance Criteria	15
ISTB-5221-1	Vertical Line Shaft Centrifugal Pump Test Acceptance Criteria	17
ISTB-5321-1	Positive Displacement Pump (Except Reciprocating) Test Acceptance Criteria	19
ISTB-5321-2	Reciprocating Positive Displacement Pump Test Acceptance Criteria	20
SUBSECTION ISTC	INSERVICE TESTING OF VALVES IN LIGHT-WATER REACTOR NUCLEAR POWER PLANTS	22
ISTC-1000	Introduction	22
ISTC-1100	Applicability	22
ISTC-1200	Exemptions	22
ISTC-1300	Valve Categories	22
ISTC-1400	Owner's Responsibility	22
ISTC-2000	Supplemental Definitions	22
ISTC-3000	General Testing Requirements	23
ISTC-3100	Preservice Testing	23
ISTC-3200	Inservice Testing	23
ISTC-3300	Reference Values	23
ISTC-3400	To Be Provided at a Later Date	23
ISTC-3500	Valve Testing Requirements	23
ISTC-3600	Leak Testing Requirements	25
ISTC-3700	Position Verification Testing	26
ISTC-3800	Instrumentation	26
ISTC-4000	To Be Provided at a Later Date	26
ISTC-5000	Specific Testing Requirements	26
ISTC-5100	Power-Operated Valves (POVs)	26
ISTC-5200	Other Valves	28

ISTC-6000	Monitoring, Analysis, and Evaluation	31
ISTC-7000	To Be Provided at a Later Date	31
ISTC-8000	To Be Provided at a Later Date	31
ISTC-9000	Records and Reports	31
ISTC-9100	Records	31
ISTC-9200	Test Plans	31
Table		
ISTC-3500-1	Inservice Test Requirements	24
SUBSECTION ISTD	PRESERVICE AND INSERVICE EXAMINATION AND TESTING OF DYNAMIC RESTRAINTS (SNUBBERS) IN LIGHT-WATER REACTOR NUCLEAR POWER PLANTS	32
ISTD-1000	Introduction	32
ISTD-1100	Applicability	32
ISTD-1400	Owner's Responsibility	32
ISTD-1500	Snubber Maintenance or Repair	32
ISTD-1600	Snubber Modification and Replacement	32
ISTD-1700	Deletions of Unacceptable Snubbers	32
ISTD-1800	Supported Component(s) or System Evaluation	33
ISTD-2000	Definitions	33
ISTD-3000	General Requirements	33
ISTD-3100	General Examination Requirements	33
ISTD-3200	General Testing Requirements	33
ISTD-4000	Specific Examination Requirements	34
ISTD-4100	Preservice Examination	34
ISTD-4200	Inservice Examination	34
ISTD-5000	Specific Testing Requirements	35
ISTD-5100	Preservice Operational Readiness Testing	35
ISTD-5200	Inservice Operational Readiness Testing	36
ISTD-5300	The 10% Testing Sample	38
ISTD-5400	The 37 Testing Sample Plan	39
ISTD-5500	Retests of Previously Unacceptable Snubbers	40
ISTD-6000	Service Life Monitoring	40
ISTD-6100	Predicted Service Life	40
ISTD-6200	Service Life Evaluation	40
ISTD-6300	Cause Determination	41
ISTD-6400	Additional Monitoring Requirements for Snubbers That Are Tested Without Applying a Load to the Snubber Piston Rod	41
ISTD-6500	Testing for Service Life Monitoring Purposes	41
ISTD-7000	Reserved	41
ISTD-8000	Reserved	41
ISTD-9000	Records and Reports	41
ISTD-9100	Snubber Records	41
ISTD-9200	Test Plans	41
ISTD-9300	Record of Tests	41
ISTD-9400	Record of Corrective Action	41
Figure		
ISTD-5431-1	The 37 Testing Sample Plan	40

Table		
ISTD-4252-1	Visual Examination Table	36
SUBSECTION ISTE	RISK-INFORMED INSERVICE TESTING OF COMPONENTS IN LIGHT-WATER REACTOR NUCLEAR POWER PLANTS	42
ISTE-1000	Introduction	42
ISTE-1100	Applicability	42
ISTE-1200	Alternative	42
ISTE-1300	General	42
ISTE-2000	Supplemental Definitions	42
ISTE-3000	General Requirements	43
ISTE-3100	Implementation	43
ISTE-3200	Probabilistic Risk Assessment	43
ISTE-3300	Integrated Decision Making	43
ISTE-3400	Evaluation of Aggregate Risk	44
ISTE-3500	Feedback and Corrective Actions	44
ISTE-4000	Specific Component Categorization Requirements	44
ISTE-4100	Component Risk Categorization	44
ISTE-4200	Component Safety Categorization	45
ISTE-4300	Testing Strategy Formulation	46
ISTE-4400	Evaluation of Aggregate Risk	46
ISTE-4500	Inservice Testing Program	47
ISTE-5000	Specific Testing Requirements	47
ISTE-5100	Pumps	47
ISTE-5200	Check Valves	48
ISTE-5300	Motor Operated Valve Assemblies	48
ISTE-5400	Pneumatically and Hydraulically Operated Valves	48
ISTE-5500	To Be Provided at a Later Date	48
ISTE-6000	Monitoring, Analysis, and Evaluation	48
ISTE-6100	Performance Monitoring	48
ISTE-6200	Feedback and Corrective Actions	49
ISTE-7000	To Be Provided at a Later Date	49
ISTE-8000	To Be Provided at a Later Date	49
ISTE-9000	Records and Reports	49
ISTE-9100	Plant Expert Panel Records	49
ISTE-9200	Component Records	49
Table		
ISTE-5121-1	LSSC Pump Testing	47
SUBSECTION ISTF	INSERVICE TESTING OF PUMPS IN LIGHT-WATER REACTOR NUCLEAR POWER PLANTS — POST-2000 PLANTS	50
ISTF-1000	Introduction	50
ISTF-1100	Applicability	50
ISTF-1200	Exclusions	50
ISTF-1300	Owner's Responsibility	50
ISTF-2000	Supplemental Definitions	50
ISTF-3000	General Testing Requirements	50
ISTF-3100	Preservice Testing	50
ISTF-3200	Inservice Testing	50
ISTF-3300	Reference Values	50
ISTF-3400	Frequency of Inservice Tests	51

ISTF-3500	Data Collection	51
ISTF-4000	To Be Provided at a Later Date	52
ISTF-5000	Specific Testing Requirements	52
ISTF-5100	Centrifugal Pumps (Except Vertical Line Shaft Centrifugal Pumps)	52
ISTF-5200	Vertical Line Shaft Centrifugal Pumps	53
ISTF-5300	Positive Displacement Pumps	54
ISTF-6000	Monitoring, Analysis, and Evaluation	55
ISTF-6100	Trending	55
ISTF-6200	Corrective Action	55
ISTF-6300	Systematic Error	55
ISTF-6400	Analysis of Related Conditions	56
ISTF-7000	Reserved	56
ISTF-8000	Reserved	56
ISTF-9000	Records and Reports	56
ISTF-9100	Pump Records	56
ISTF-9200	Test Plans	56
ISTF-9300	Record of Tests	56
ISTF-9400	Record of Corrective Action	56
Tables		
ISTF-3000-1	Inservice Test Parameters	51
ISTF-3510-1	Required Instrument Accuracy	52
ISTF-5120-1	Centrifugal Pump Test Acceptance Criteria	53
ISTF-5220-1	Vertical Line Shaft and Centrifugal Pump Test Acceptance Criteria	54
ISTF-5320-1	Positive Displacement Pump (Except Reciprocating) Test Acceptance Criteria	55
ISTF-5320-2	Reciprocating Positive Displacement Pump Test Acceptance Criteria	55
Mandatory Appendices		
I	Inservice Testing of Pressure Relief Devices in Light-Water Reactor Nuclear Power Plants	57
II	Check Valve Condition Monitoring Program	73
III	Preservice and Inservice Testing of Active Electric Motor Operated Valve Assemblies in Light-Water Reactor Power Plants	75
IV	Intentionally Left Blank	80
V	Pump Periodic Verification Test Program	81
Nonmandatory Appendices		
A	Preparation of Test Plans	82
B	Dynamic Restraint Examination Checklist Items	85
C	Dynamic Restraint Design and Operating Information	86
D	Comparison of Sampling Plans for Inservice Testing of Dynamic Restraints	87
E	Flowcharts for 10% and 37 Snubber Testing Plans	88
F	Dynamic Restraints (Snubbers) Service Life Monitoring Methods	91
G	Application of Table ISTD-4252-1, Snubber Visual Examination	93
H	Test Parameters and Methods	95
J	Check Valve Testing Following Valve Reassembly	97
K	Sample List of Component Deterministic Considerations	98
L	Acceptance Guidelines	99
M	Design Guidance for Nuclear Power Plant Systems and Component Testing	102

DIVISION 2: OM STANDARDS

CONTENTS

PART 2	PERFORMANCE TESTING OF CLOSED COOLING WATER SYSTEMS IN LIGHT-WATER REACTOR POWER PLANTS	113
PART 3	VIBRATION TESTING OF PIPING SYSTEMS	114
1	Scope	114
2	Definitions	114
3	General Requirements	115
4	Visual Inspection Method	119
5	Simplified Method for Qualifying Piping Systems	119
6	Rigorous Verification Method for Steady-State and Transient Vibration	124
7	Instrumentation and Vibration Measurement Requirements	125
8	Corrective Action	126
Figures		
1	Typical Components of a Vibration Monitoring System (VMS)	115
2	Deflection Measurement at the Intersection of Pipe and Elbow	120
3	Single Span Deflection Measurement	120
4	Cantilever Span Deflection Measurement	120
5	Cantilever Span/Elbow Span in Plane Deflection Measurement	120
6	Cantilever Span/Elbow Guided Span in Plane Deflection Measurement	121
7	Span/Elbow Span Out-of-Plane Deflection Measurement, Span Ratio < 0.5	121
8	Span/Elbow Span Out-of-Plane Deflection Measurement, Span Ratio > 0.5	121
9	Span/Elbow Span Out-of-Plane Configuration Coefficient Versus Ratio of Spans	121
10	Correction Factor C_1	123
Tables		
1	System Tolerances	117
2	Examples of Specifications of VMS Minimum Requirements	126
Nonmandatory Appendices		
A	Instrumentation and Measurement Guidelines	127
B	Analysis Methods	130
C	Test/Analysis Correlation Methods	131
D	Velocity Criterion	132
E	Excitation Mechanisms, Responses, and Corrective Actions	133
F	Flow Chart — Outline of Vibration Qualification of Piping Systems	135
G	Qualitative Evaluations	137
H	Guidance for Monitoring Piping Steady-State Vibration Per Vibration Monitoring Group 2	138
I	Acceleration Limits for Small Branch Piping	143

PART 12	LOOSE PART MONITORING IN LIGHT-WATER REACTOR POWER PLANTS.....	145
1	Introduction.....	145
2	Definitions.....	145
3	References.....	146
4	Equipment.....	147
5	Program Elements.....	157
6	Documentation.....	161
Figures		
1	Typical Broadband Sensor Response to Nearby Impact.....	148
2	Typical Broadband Sensor Response to More Distant Impact.....	148
3	Range of Loose Part Signal Amplitude and Predominant Frequency Content.....	149
4	Field Equipment.....	149
5	Direct Stud Mount.....	150
6	Clamped Mount.....	150
7	Recommended Sensor Array for PWR With U-Tube Steam Generator.....	152
8	Recommended Sensor Array for PWR With Once-Through Steam Generator.....	153
9	Recommended Sensor Array for BWR.....	154
10	Block Diagram for Charge Converter Calibration Tests.....	158
11	Cable Properties.....	159
Tables		
1	Recommended PWR Accelerometer Locations.....	151
2	Recommended BWR Accelerometer Locations.....	153
Nonmandatory Appendix		
A	References.....	162
PART 16	PERFORMANCE TESTING AND INSPECTION OF DIESEL DRIVE ASSEMBLIES IN LIGHT-WATER REACTOR POWER PLANTS.....	163
1	Introduction.....	163
2	Post-Major Maintenance Check.....	166
3	Testing.....	166
4	Inservice Testing of Components.....	167
5	Other Diesel Drive Testing Guidelines.....	171
6	Alarm and Shutdown During Tests.....	171
7	Engine Operating Data and Records.....	172
Figure		
1	Boundary and Support Systems of Emergency Diesel Generator Systems.....	164
Nonmandatory Appendices		
A	Post-Major Maintenance Test Data.....	173
B	Functional/Inservice Test Data.....	174
C	Data Trending Examples.....	175
PART 21	INSERVICE PERFORMANCE TESTING OF HEAT EXCHANGERS IN LIGHT- WATER REACTOR POWER PLANTS.....	181
1	Introduction.....	181
2	Definitions.....	181

3	References	183
4	Selection and Prioritization of Heat Exchangers	184
5	Basic Requirements	184
6	Selection of Methods	185
7	Testing and Monitoring Conditions	193
8	Errors, Sensitivities, and Uncertainties	194
9	Acceptance Criteria	195
10	Corrective Action	196
11	Records and Record Keeping	196
Figures		
1	Intervals, Limits, and Parameter Trending (Typical)	186
2	Method Selection Chart	187
Nonmandatory Appendices		
A	Diagnostics	198
B	Precautions	201
C	Examples	204
PART 24	REACTOR COOLANT AND RECIRCULATION PUMP CONDITION MONITORING	235
1	Introduction	235
2	Definitions	235
3	References	237
4	Machine Faults	237
5	Vibration, Axial Position, and Bearing Temperature Monitoring Equipment	237
6	Vibration Data Analysis System Requirements	240
7	Seal Monitoring	242
8	Vibration, Axial Position, and Bearing Temperature Monitoring	243
9	Alarm Settings	245
10	Analysis and Diagnostics	246
11	Additional Technologies	247
12	Other	248
Tables		
1	Pumpset Mechanical Faults	238
2	Seal Faults	238
3	Electrical Motor Faults	239
4	Minimum Monitoring and Recording Intervals	243
5	Typical Thrust Position Alarm Setpoints for a Pump With Normal Upthrust	246
Nonmandatory Appendices		
A	References	249
B	Thermography	250
C	Lube Oil Analysis	251
D	Motor Current Signature Analysis	252
E	Loose Parts Monitoring	253
PART 25	PERFORMANCE TESTING OF EMERGENCY CORE COOLING SYSTEMS IN LIGHT-WATER REACTOR POWER PLANTS	254

PART 26	DETERMINATION OF REACTOR COOLANT TEMPERATURE FROM DIVERSE MEASUREMENTS	255
1	Introduction	255
2	Definitions	255
3	References	256
4	Requirements	256
5	Develop Test Procedures and Perform Testing	256
6	Documentation	258
Nonmandatory Appendix		
A	Measurement Equipment Uncertainties	259
PART 28	STANDARD FOR PERFORMANCE TESTING OF SYSTEMS IN LIGHT-WATER REACTOR POWER PLANTS	260
1	Introduction	260
2	Definitions	260
3	References	261
4	General Testing Requirements	261
5	Specific Testing Requirements	266
6	Evaluate Test Data	266
7	Documentation	266
Mandatory Appendices		
I	Specific Testing Requirements of Emergency Core Cooling Systems in BWR Power Plants	268
II	Specific Testing Requirements of Emergency Core Cooling Systems in PWR Power Plants	272
III	Specific Testing Requirements of Auxiliary or Emergency Feedwater Systems in LWR Power Plants	275
IV	Specific Testing Requirements of Closed Cooling Water Systems in LWR Power Plants	277
V	Specific Testing Requirements of Emergency Service Water Systems in LWR Power Plants (Open Cooling Water Systems)	281
VI	Specific Testing Requirements of Instrument Air Systems in LWR Power Plants	284
Nonmandatory Appendices		
A	Industry Guidance	289
B	Guidance for Testing Certain System Characteristics	293
C	Measurement Accuracy of System Characteristics	299
PART 29	ALTERNATIVE TREATMENT REQUIREMENTS FOR RISC-3 PUMPS AND VALVES	306
1	Introduction	306
2	Definitions	306
3	General Programmatic Requirements for RISC-3 Pumps and Valves	306
4	Alternative Treatment for Reasonable Confidence of RISC-3 Pump and Valve Performance	307
5	Corrective Action	307
6	Feedback and Treatment Adjustment	308
7	Records	308

DIVISION 3: OM GUIDES

CONTENTS

PART 5	INSERVICE MONITORING OF CORE SUPPORT BARREL AXIAL PRELOAD IN PRESSURIZED WATER REACTOR POWER PLANTS	312
1	Purpose and Scope	312
2	Background	312
3	Program Description	314
4	Baseline Phase	314
5	Surveillance Phase	316
6	Diagnostic Phase	316
Figure		
1	Reactor Arrangement Showing Typical Ex-Core Detector Locations	313
Table		
1	Summary of Program Phases	315
Nonmandatory Appendices		
A	Theoretical Basis	318
B	Data Reduction Techniques	320
C	Data Acquisition and Reduction	322
D	Data Evaluation	325
E	Guidelines for Evaluating Baseline Signal Deviations	329
F	Correlation of rms Amplitude of the Ex-Core Signal (Percent Noise) and Amplitude of Core Barrel Motion	334
G	Bibliography	335
PART 7	REQUIREMENTS FOR THERMAL EXPANSION TESTING OF NUCLEAR POWER PLANT PIPING SYSTEMS	336
1	Scope	336
2	Definitions	336
3	General Requirements	337
4	Reconciliation Methods	338
5	Corrective Action	340
6	Instrumentation Requirements for Thermal Expansion Measurement	340
Figures		
1	System Heatup, Reconciliation, and Corrective Action	339
2	Typical Components of a TEMS	341
Table		
1	An Example of Specification of TEMS Minimum Requirements	341
Nonmandatory Appendices		
A	Guidelines for the Selection of Instrumentation and Equipment of a Typical TEMS	343
B	Thermal Stratification and Thermal Transients	346

PART 11	VIBRATION TESTING AND ASSESSMENT OF HEAT EXCHANGERS	349
1	Introduction	349
2	Definitions	349
3	References	349
4	Background Description	349
5	Selection of Equipment to Be Tested	350
6	Selection of Test Method	351
7	Test Requirements	352
8	Test Conditions	359
9	Documentation	359
10	Precautions	359
Figure		
1	Tube Bundle Configuration With Tube Groupings Most Susceptible to Fluidelastic Instability Denoted by Cross-Hatching	353
Nonmandatory Appendices		
A	Causes of Vibration	360
B	Methods for Comparative Evaluation of Fluidelastic and Turbulence- Induced Vibration	364
C	Test Guidelines for Dynamic Characterization of Tubes	367
D	External Vibration Surveys	368
E	Detection Methods and Data Interpretation	369
F	Vibration Acceptance Guidelines	384
G	Installation of Strain Gages	386
PART 14	VIBRATION MONITORING OF ROTATING EQUIPMENT IN NUCLEAR POWER PLANTS	387
1	Introduction	387
2	Definitions	387
3	References	388
4	Vibration Monitoring	389
5	Establishing the Baseline	393
6	Establishing Vibration Limits	395
7	Data Acquisition	397
8	Hardware	398
9	Diagnostics	398
Figures		
1	An Example of a Vibration Data Sheet	394
2	An Example of a Vibration Trend Curve	395
3	Vibration Level Trend Plot of Condition One	396
4	Vibration Level Trend Plot of Condition Two	397
Tables		
1	Comparison of Periodic and Continuous Monitoring and Relative Advantages	389
2	Transducer Location Guidelines — Turbines	390
3	Transducer Location Guidelines — Equipment With Antifriction Bearings	390

4	Transducer Location Guidelines — Horizontal Pumps — Fluid Film Bearings	391
5	Transducer Location Guidelines — Motor-Driven Vertical Pumps — Fluid Film Bearings	391
6	Transducer Location Guidelines — Electric Motors	392
7	Vibration Troubleshooting Chart	399
Nonmandatory Appendices		
A	Instrumentation Selection and Use	400
B	Transducers and Analysis Equipment	402
PART 17	PERFORMANCE TESTING OF INSTRUMENT AIR SYSTEMS IN LIGHT-WATER REACTOR POWER PLANTS	407
PART 19	PRESERVICE AND PERIODIC PERFORMANCE TESTING OF PNEUMATICALLY AND HYDRAULICALLY OPERATED VALVE ASSEMBLIES IN LIGHT-WATER REACTOR POWER PLANTS	408
1	Introduction	408
2	Definitions	408
3	Test Guidance	409
4	Test Methods	409
5	Analysis and Evaluation of Data	410
6	Corrective Action	411
PART 23	INSERVICE MONITORING OF REACTOR INTERNALS VIBRATION IN PRESSURIZED WATER REACTOR POWER PLANTS	412
1	Introduction	412
2	Definitions	412
3	References	414
4	Internals Vibration Excitation Sources, Responses, and Modes	415
5	Signal Database	415
6	Data Review	420
Figures		
1	Schematic of a Pressurized Water Reactor (PWR) Showing Typical Sensor Arrangement	413
2	Beam and Shell Mode Vibration of a PWR Core Support Barrel	416
3	Typical Components in a Signal Data Acquisition System	418
Tables		
1	Sensor Types and Potential Applications in Reactor Noise Analysis	417
2	Relationships Between Sampling Rates and Analysis Results	418
Nonmandatory Appendices		
A	Discussion of Spectral Functions	422
B	Supporting Information on Component Vibrations	426
C	Pump-Induced Vibrations	428
D	Sampling Rate and Length of Data Record Requirement to Resolve a Spectral Peak	434